

## CORRIGENDUM-I

Date:15/10/2015

Pre-Bid Meeting Date: 06/10/2015

Name of work: - SHIFTING OF WATER SUPPLY PIPELINES OF DIFFERENT DIA METERS ALONG METRO RAIL ALIGNMENT FOR PRIORITY SECTION FROM MUNJE CHOWK TO MIHAN AND OTHER LOCATION


E-Tender No : - NMRCL/U/S (WP)/02-2015  
Tender No (Portal): -17

| Sr. No. | Quarries  | Clarifications  |
|---------|---|---|
| 1       | Item No.7 Lowering –laying of 450MM D I pipes is not considered   | Will be paid as per conditions of Schedule 'C'                  |
| 2       | Item No. 8 Lowering laying of MS special- Diameters is not mentioned  | Read as:<br>1.5mm to 8mm thick<br>2.Above 250mm .Upto 500mm dia |
| 3       | Item No. 11 Providing Cutting and binding steel for Thurst block it is said 0.80 MT per CUM and the rate mentioned is per MT. please clarify the above. | Unit to be read as cum.   |
| 4       | Item No.14 Providing MS plates, please clarify the mode of measurement per flange or per plate in KG. As considered the wastage of plate cutting.       | Unit per Kg. prevails   |
| 5       | Item No.17 & 18 For sluice valve & butterfly valve PN rating is not mentioned.  | PN -1.6 for pumping mains<br>PN -1.0 for distribution mains     |
| 6       | Item No. 19 Lowering laying of 450MM sluice valve is not considered   | As per (1) above  |
| 7       | Item No. 32 Kinetic Air valve 80MM PN rating is not mentioned   | As per Five (5) above   |
| 8       | Item No.33 For this quantity & rate is blank  | As per (1) above  |
| 9       | Item No. 35 paving blocks M40 -50MM thickness unit is per CUM. Please clarify the unit.   | Read as Sq.mt.  |
| 10      | Item No.36 Chequered color tiles unit is per CUM. Please clarify the unit.  | Read as Sq.mt.  |



|    |  |  |
|----|--|--|
| 11 | Item No.37 please clarify the Item if it is filling in plinth by murum or by sand  | Item No. 37 prevails   |
| 12 | Item No. 38 Filling sand boxing unit is per RMT. Please clarify the Unit   | Read as cubic meter  |
| 13 | Whether the unregistered contractors are eligible for the bid of shifting of water supply pipe lines                           | Only Registered contractors are eligible   |
| 14 | Total quantity of DI pipe procurement (lt. Nos) is 16400m where as lowering, laying of only 10500m is shown under to be wrong  | Quantity executed shall be paid as per rates provided in BOQ and thereafter provision of clause No.38 will prevail |
| 15 | Item No.11 is for providing, cutting , bending placing reinforcement, the rate is shown as 5867.44/MT which seems to be wrong. | Read as Cubic Meter.   |
| 16 | Item No.30: Item is for balling out of water unit mentioned is BHP, which should be BHP.Hr.                                    | Read as BHP/Hr.  |
| 17 | Item No.32 Unit of air valve is shown as M which should be per number  | Read as number   |
| 18 | Item No.35&36- Unit of paving block & titles should be per m2 & not m3 as shown in schedule B                                  | Read as Sq. Mt.  |
| 19 | Item No.38 : Item is for sand boxing the unit mentioned is "per rmt" This needs clarification                                  | Read as Cubic Meter  |

Note: It is brought to the notice of all prospective bidders that the nature of work is diversion of existing underground water supply lines which are infringing with entire metro alignment. The work is to be executed as and when required during contract period

  
General Manager (Pr.)  
NMRCCL, Nagpur