

Nagpur Metro Rail Corporation Limited

Name of Work: Supply, Installation, Testing and commissioning of Ballasted/BALLASTLESS Track in at Grade Section of NORTH-SOUTH Corridor along with Ballasted/ embedded Track in Mihan Depot of Nagpur Metro Rail Project

Tender no ICB: N1T-06/2016

Corrigendum No II

Tender No. (As uploaded in the E-Tender Portal): - No 54

Date: 23/07/2016

| Sr. No | Clause | Description | Existing | Revised |
|--------|---|--|---|---|
| 1 | Section 3. Eligibility and qualification criteria | No of senior Site supervisor | 01 | 04 |
| 2 | Section III. cl.3.6 | List of equipment's | Track is to be laid using Track Master | Track is to be laid using Track Master or equivalent equipment. |
| 3 | Part 1. Section IV. Bidding form | 4.4 Bidders technical submission Para. g | Methodology of pumping / transportation of RMC from ground level to tunnel for longer distance pumping as may be required in some portion of tunnels in this project. | Tunnel may be read as viaduct. |
| 4 | Part1. Section III.cl.4.2(a) | Specific construction and contract management experience | Ballasted Track | May read as Ballasted/Ballastless Track |
| 5 | Part 2. Work Requirement. (PS) cl. 8.12.1 | Permanent Markers | Kilometre Markers | Kilometre Markers may be read as Kilometre Markers and Hectometer Markers |

| | | | | |
|---|---|---|---|---|
| 6 | Part 4. Bill of Quantity, Bill No. SPM1. Item no. 4.4 | Supply of Permanent way material | Plate screws as per RDSO Drg. No T-3914 | Plate screws as per RDSO Drg. No T-3914 (Galvanised) |
| 7 | Part 4. Bill of Quantity, Bill No. SPM1. Item no. 5 | Supply of Permanent way material – fish plate | Quantity in sets | One set comprising of 2 fish plates, 2 clamps and 4 bolts and nuts. |
| 8 | Part 2. Particular specification, scope of work item 2.2 General criteria and Track Parameters, 2.2.1 | Track Centres | | Track centre for track will be 4.1 metre excluding for scissor cross over which is 4.5 metre. |



General Manager/ (Procurement)
Nagpur Metro Rail Corporation Limited